电力工业电气设备质量检验测试中心



Quality Inspection and Test Center for Equipment of Electric Power









JHG616 号

检测报告



Inspection Report

地 址: 湖北省武汉市洪山区珞喻路 143 号

邮 编: 430074

电 话: 4006565689

传 真: (027) 59832255

网 址: China-qitc.sgepri.sgcc.com.cn

Quality Inspection and Test Center for Equipment of Electric Power Inspection Report

(2012)QITC No.JHG 616

Client: Guangdong Sihui Instrument Transformer Works Co., Ltd

Description of Sample

Name of test sample: Inductive voltage transformer

Type: SSVT-550

Sample NO.: V1207500001

Manufacturer: ABB S.p.A.-Power Products Division U.O.Adda-HV

Date of Manufacture: July -2012 Sampling way: offer by client

Inspection Standard/Reference

GB1207-2006 Inductive voltage transformers

DL/T726-2000 Specification of voltage transformer for electrical power for order IEC60044-2:2003 Instrument transformers –Part 2: Inductive voltage transformers

Category of Inspection: Routine test /Type test/Special test

Inspection Dates: From 2012–10-29 to 2012–12–30

Conclusion:

Inductive voltage transformer with the type of SSVT-3, 0 offered by Guangdong Sihui Instrument Transformer Works Co.,Ltd meets the requirements of the corresponding items of the standards GB1207—2006,etc.

Note: This English report is written at request of the client. In the event of any difference in meanings of the text, the Chinese report shall take precedence over the English version.

Valid Time 5 years

Inspected by:

Checked by:

Examined and verified by:

Approved by:

Date of issue:

313-02-01

Testing Item and Conclusion

No.	Item	Reference standard	Test result	Conclusion
1	Inspection semblance and verification of terminal markings	The nameplate, sign, earthing terminal, terminal marking shall meet the requirements. The valve and the blast slice shall be entireness.	OK	Pass
2	Power-frequency withstand test on secondary windings	Applied voltage on winding-to-winding and winding-to-earth shall be 3kV/50Hz/1min	Winding-to-winding and winding-to-earth Test voltage 3kV/50Hz/1min No disruptive puncture occurs.	Pass
3	Power frequency withstand test on earthed terminal of primary winding	Applied voltage between earthed terminal of primary winding and earth shall be 5kV/50Hz/1min	Test voltage 5kV/50Hz/1min No disruptive puncture occurs.	Pass
4	Induced voltage withstand test on primary windings	Induced voltage of the primary winding shall be 680kV/150Hz/40s	Atmosphere correction factor K _c =1.008 Test voltage 680kV/150Hz/40s No disruptive puncture occurs. Dry bulb temperature 27°C Wet bulb temperature 23°C Atmosphere pressure 100.9kPa	Pass
5	Partial discharge measurement	Testing frequency 150 Hz Pre-stress voltage 680 kV Test voltage 550 kV PD≤ 10 pC Test voltage 381 kV PD≤ 5 pC	Testing frequency 150 Hz Pre-stress voltage 680 kV Test voltage 550 kV PD 5 pC Test voltage 381 kV PD 3 pC Backgroundlevel 1.5 pC Ambienttemperature 27 °C Relativehumidity 66 %	Pass
6	Measurement of Excitation	Providing the test data	Details in appendix No. C.	
7	Determination of errors	The errors of the second windings should fulfill the requirement of class 0.5.	The errors of secondary windings are measured at rated frequency and rated power factor within rated burden. Details in appendix No. D	Pass
8	Measurement of DC resistances	Providing the test data	AN: 229.9 Ω la1n: 178.2 mΩ Ambient temperature 27°C	

No.	Item	Reference standard	Test result	Condusion
9	Temperature rise test	The temperature rise of windings cannot exceed 75K under the voltage of 1.2Un. The temperature rise of windings cannot exceed 10K under the voltage of 1.5Un (30s) (beginning from the normality).	The voltage of 1.2Un is applied to primary winding when the secondary winding an load thermal limiting burden 200VA. After every part reaching a steady state, the values of temperature rise are shown as follows AN: 8 K an: 27 K Ambient temperature 27 °C The voltage of 1.5Un is applied to primary winding for 30s beginning from the normality when the secondary windings load rated burden. After every part reaching a steady state, the values of temperature rise are shown as follows AN: 1.0 K an: 1.5 K Ambient temperature 27 °C The details of 1.2Un in appendix No. E	Pass
10	Lightning impulse test and chopped impulse test on primary winding	Applied voltage on primary winding to secondary windings and earth shall be Standard LI 1550 kV Waveform 1.2/50 µs positive impulses 3 times negative impulses 3 times Standard LI-chopped 1783kV Waveform (2~5)µs negative impulses 2 times	3 consecutive LI in positive and negative polarities and two chopped LI in negative polarity were applied to primary terminal. Details in appendix No. F No disruptive puncture occurs.	Pass
11	Switching impulse test	Water resistance 100±15 Ω • m at 20°C Vertical precipitation1.0~2.0mm/min Horizontal precipitation1.0~2.0mm/min Standard LI 1175kV Waveform 250/2500μs positive impulses 15 times	Water resistance 105 Ω • m at 20°C Vertical precipitation 1.2mm/min Horizontal precipitation1.2mm/min 15 Standard LI in positive polarity are applied to primary terminal. Details in appendix No. G No disruptive puncture occurs.	Pass
12	Short-circuit withstand capability test	The rated voltage 7.2kV is applied to secondary windings for 1.0s when primary winding is connected with the ground. There shall be no electrical and mechanical damage.	Secondary voltage 7.2 kV Secondary current 490 A Durative time 1.04 s Waveform in appendix No. H There is no electrical and mechanical damage. NOTE 1. The primary conductor is copper stick, the current density is 5.2A/mm². 2. The secondary conductor is copper stick., the current density is 12.3A/mm².	Pass

No.	Item	Reference standard	Test result	Conclusion
13	Power-frequency voltage withstand test on secondary windings (retrial)	Applied voltage on winding-to-winding and winding-to-earth shall be 3kV/50Hz/1min	Test voltage 3kV/50Hz/1min No disruptive puncture occurs.	Pass
14	Power frequency withstand test on earthed terminal of primary winding (retrial)	Applied voltage between earthed terminal of primary winding and earth shall be 5kV/50Hz/1min	Test voltage 5kV/50Hz/1min No disruptive puncture occurs.	Pass
15	Induced voltage withstand test on primary winding (retrial)	Induced voltage of the primary windings shall be 612kV/150Hz/40s	Test voltage 612kV/150Hz/40s No disruptive puncture occurs.	Pass
16	Partial discharge measurement (retrial)	Testing frequency150 HzPre-stress voltage612 kVTest voltage550 kVPD≤10 pCTest voltage381 kVPD≤5 pC	Testing frequency Pre-stress voltage 612 kV Test voltage 550 kV PD 7 pC Test voltage 381 kV PD 3 pC Backgroundlevel 1.9 pC	Pass
17	Measurement of Excitation (retrial)	Providing the test data	Magnetizing current at rated voltage 5.6mA	
18	Determination of errors (retrial)	The errors of the second windings shall meet the requirement of class 0.5.	Details in appendix No. I.	Pass
19	Radio interference voltage measurement	The radio interference voltage at 349kV shall not exceed 500 μ V	Test voltage 349kV Radio interference voltage doesn't exceed 300 µ V (0.5MHz)	Pass
20	Mechanical test	The test loads shall be applied for 2.5kN ,60s for each of the conditions. And there should be no evidence of damage (deformation, rupture or leakage).	Horizontal(landscape orientation) to primary terminals 2.5kN, 1min Horizontal(longitudinal orientation) to primary terminals 2.5kN, 1min Vertical to primary terminals 2.5kN, 1min There is no evidence of damage (deformation, rupture or leakage).	Pass
21	The gas seal test	The relative ratio of gas giving off in one year should not exceed 0.5% at the rated pressure of 0.65MPa.	The relative ratio of gas giving off in one year doesn't exceed 0.1%	Pass
22	Measurement of the water contained in gas	The water contained in gas shall be less than 150μL/L	The water contained in gas is 75µL/L	Pass

No.	Item	Reference standard	Test result	Conclusion
23	nrimary winding	In the case of no displayed pressure, The test voltage (318kV) shall be applied between the terminal of the primary wind and earth for 5min. The terminals of the secondary windings shall be connected to earth.	pressure	Pass
24	Inspection of core	Clear, no displacement, no distortion. The sizes should accord with the requirements of design.	OK Photographs in appendix No.K	Pass

Note

- 1. Main test circuits, Details in appendix No. J.
- 2. The tests of 1~19 items were performed in the pressure of 0.55MPa. The tests of 20~22 items were performed in the rated pressure of 0.65MPa.
- 3. The outer insulation of object is electrotechnical methyl-silicone rubber bushing. Creepage distance of external insulation is 14.34 m, and arc flash distance is 3.81 m.
- 4. In addition to the above tests, the outline dimension was measured according to the requirements of factory (measuring positions and numbers in appendix No. L); Results of load loss measurement, no-load voltage ratio measurement, temperature rise test in appendix No. M.

Appendix No. A Main characteristic Parameters of the Sample

Description: Inductive voltage transformer

Sample NO.: V1207500001

Type: SSVT-550

Highest voltage for equipment: 550kV

Rated voltage: 525kV

Rated frequency: 50 Hz

Rated transformation: $525000/\sqrt{3}$ / 7200V

Rated insulation level: 550/680/1550/1175kV

Date of Manufacture:

July-2012

Secondary windings Accuracy class	an
Rated burden (VA) Power factor (0.8)	0~200

Appendix No. B Parameters of the main equipment


No.	Description/Type	Serial No.	Technical parameter	Accuracy class or uncertainty	Calibration institution	Valid date
1	Voltage transformer for measuring service HJ3-765	#05001 (YQ359)	$765/\sqrt{3} \text{ kV}$ $100/\sqrt{3} \text{ V}$	0.02	National center for high voltage measurement	2014.08.17
2	Inductive voltage divider FGB-02	#4447 (YQ317)	(0~200)V	0.0002	National center for high voltage measurement	2014.01.13
3	Instrument transformer test set HE20	#06104 (YQ382)	100、100/√3 V	2	National center for high voltage measurement	2014.01.12
4	Partial discharge detector JFD-251	#20051112 (YQ381)	(0.5~2000)pC	10	National center for high voltage measurement	2013.08.30
5	Electromagnetic interference measuring receiver ZN3950	#051205 (YQ392)	150kHz~ 30MHz	<±1kHz	Wu Han measurement center of Yawp	2013.04.10

Appendix No. C Measurement of Excitation

Percentage of rated secondary voltage (%)	20	50	80	100	120	150	
No-load secondary current (mA)	1.6	4,4	6.2	5.5	18.4	158	
Ambient temperature	`		Relative	humidity	66 %		

Appendix No. D Determination of errors

1. Test circuits



TT: Testing transformer

Tx: Object voltage transformer

To: standard voltage transformer


2. Test result

Secondary	Accuracy	Епог	Percent	age of rated	Burden /(VA/cos Φ)	
windings	class	CHOI	80	100	120	an
		Ratio error(%)	-0.05	-0.05	-0.10	200
on	0.5	Phase displacement('	-2	-2	0	0.8
an	0.5	Ratio error(%)	-0.05	-0.05	-0.10	
		Phase displacement('	-2	-2	0	0
Ambient temperature		27 ℃	Relat	ive humidity	66 %	

Appendix No. E Temperature rise test 1.2Un


Temperature-rising curve of AN The thermal resistance of $R2=236.55 \Omega$

绕组热态电阻温升曲线 热态电阻R2=236.55♀



Temperature-rising curve of an The thermal resistance of R2=0.19667 Ω

绕组热态电阻温升曲线 热态电阻R2=0.19667Ω



Appendix No. F Lightning impulse test and chopped lighting impulse test

1. Atmosphere conditions


Ambient temperature

7 °C

Relative humidity

% 60

2. Test circuits



R_{S2}: front resistance

g₂: chopping sphere gap

 Z_1 , Z_2 : divider

R_P: tail resistance

C₁: front capacitor T_x: object

gl: discharging sphere gap


C2: tail capacitor V: voltage meter

3. Test results

No.	The standard voltage(peak) (kV)	Waveform of voltage	The test voltage (peak) (kV) (kV)	The chopped time(µs)	Waveform No.	Result	Remarks
1	775	Pos.LI	983	/	1	OK	/
2	1550	Pos.LI	1580	/	2	OK	/
3	1550	Pos.LI	1571	/	3	OK	/
4	1550	Pos.LI	1557	_/	4	OK	/
5	775	Neg.LI	967	/	5	OK	/
6	1550	Neg.LI	1568	/	6	OK	/
7	892	Chopped Neg.LI	983	4.4	7	OK	/
8	1783	Chopped Neg.LI	1716	4.5	8	OK	/
9	1783	Chopped Neg.LI	1759	4.5	9	OK	/
10	1550	Neg.LI	1576	/	10	OK	/
11	1550	Neg.LI	1553	/	11	OK	/

4. Conclusion





Appendix No. G Switching impulse test

1. Atmosphere conditions

Water resistance: $105 \Omega \cdot m$ at $20 ^{\circ}C$

Vertical precipitation: 1.2mm/min Horizontal precipitation: 1.2mm/min

2 Test results


\ lest re	suits						
1	588	Pos.SI	703	/	1	OK	/
2	1175	Pos.SI	1177	/	2	OK	/
3	1175	Pos.SI	1172	1	3	OK	/
4	1175	Pos.SI	1174	/	4	OK	/
5	1175	Pos.SI	1174	/	5	OK	/
6	1175	Pos.SI	1160	/	6	OK	/
7	1175	Pos.SI	1173	/	7	OK	/
8	1175	Pos.SI	1165	1	8	OK	/
9	1175	Pos.SI	1177	/	9	OK	/
10	1175	Pos.SI	1175	/	10	OK	/
11	1175	Pos.SI	1173	/	11	OK	/
12	1175	Pos.SI	1173	1	12	OK	/
13	1175	Pos.SI	1171	/	13	OK	/
14	1175	Pos.SI	1165	/	14	OK	/
15	1175	Pos.SI	1172	/	15	OK	/
16	1175	Pos.SI	1175	/	16	OK	/


3. Conclusion Pass

Appendix referential Waveform

(231/1600 µ s)


MUNICAL VIEW





Appendix No. H Endurance of short circuit

1. Test circuits




TV: AC voltage regulator TA: Measuring current transformer

TT: Transformer

r OSC: Recording oscillograph
Tx: Object voltage transformer

S: Switch V: Voltage meter




Appendix No. I Determination of errors(retrial)

Secondary	condary Accuracy			Percentage of rated current			Burden cosφ					
windings class	class	Еггог		EITOF		EIO		80	1	00	120	an
		Ratio error(%)		-0.05	-0).05	-0.10	200				
~		Phase displacement(')		-2		-2	0	0.8				
an	0.5	Ratio error(%) Phase displacement(')		-0.05	-0).05	-0.10					
				-2	-2		0	0				
Ambient temperature		6℃		Rela	ative humidity	61 %						

Appendix No. J Main test circuits


Figure 1——Power-frequency withstand test on primary windings



 $\begin{array}{ll} C_a & & \\ C_k & & \\ \end{array} \\ Coupling \ capacitor$

Z—filter (there is no need if C_k is capacitance of testing transformer)

Figure 2——Partial discharge measurement



—testing transformer

-Object

-Coupling capacitor

M—measurement of partial discharge


 $Z_{\rm m}$ —testing impedance

Z——filter (there is no need if C_k is capacitance of testing transformer)


Appendix No. K Inspection of core







Appendix No. L Dimension measurement



Unit: mm

1	952
2	6139
3	1582
4	1749
5	831
6	30.2
7	830
8	81
9	40.1

 $\hbox{Appendix No.}\,M$

No.	Item	Entrusted requirements	Test result	Conclusion
1	Load loss measurement	Power frequency current 46.25 A is applied to secondary winding when primary winding is short circuit. Root mean square voltage active power absorbed shall be measured.	condary exciting current:46.25 A condary voltage: 665 V ad loss: 1216 W bient temperature: 26°C lative humidity: 57%	
2	Temperature rise test	Power frequency current 46.25A is applied to the secondary winding when primary winding is short circuit. The temperature rise of windings cannot exceed 75K	Power frequency current 46.25A is applied to the secondary winding when primary winding is short circuit. After every part reaching a steady state, the values of temperature rise are shown as follows AN: 45 K an: 68 K Ambient temperature 26 °C	
3	No-load voltage ratio measurement	No-load voltage ratio shall not exceed $\pm 0.5\%$ of the rated voltage ratio.	an: -0.09% Ambient temperature:26°C Relative humidity:57%	

Note: The above tests were performed in the pressure of 0.55MPa.